

MGP Remediation Goshen, IN



Project Description

Northern Indiana

- 20,000 cubic yards of soil excavated
- 100 individual well points installed for dewatering
- Over 1,000,000 gallons of water treated and discharged to local WWTP
- Project completed during winter months of 2015
- 200+ feet of temporary shoring installed
- 400 feet of 18-inch RCP storm sewer installed
- 20 foot deep 8 foot diameter interceptor structure installed

Project Details

- **Date:** Winter 2015
- **Client:** NiSource
- **Location:** Goshen, IN

Project Gallery

